Exhibit D: ENGINEERING DESIGNS 2



GENERAL NOTES

ALL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES. SEE ARBO II GENERAL CONSERVATION MEASURES (DRAWINGS 1.1 - 1.2) AND LAMPREY AND FRESHWATER MUSSEL CONSERVATION MEASURES (DRAWINGS 1.3 - 1.4).

CARE AND DIVERSION OF WATER NOTES

- 1. CONTRACTOR SHALL SUBMIT A DEWATERING AND WORK AREA ISOLATION (STREAM BYPASS) PLAN THAT LIMITS DEWATERED STREAM LENGTH TO PROJECT ENGINEER FOR APPROVAL PRIOR TO BEGINNING CONSTRUCTION. IT IS ANTICIPATED THAT THE WORK AREA WILL BE DRY DURING CONSTRUCTION.
- 2. THE PREFERRED WORK AREA ISOLATION TECHNIQUE SHALL INCORPORATE PUMPING WHEN NEEDED TO REDUCE TURBIDITY IN THE WORK AREA.
- STATIONARY POWER EQUIPMENT, SUCH AS GENERATORS, WITHIN 150-FEET OF THE WATER SHALL HAVE SECONDARY CONTAINMENT TO PREVENT SPILLS OR LEAKS FROM REACHING THE WATER.
- ALL POWER EQUIPMENT WITHIN 150-FEET OF THE WATER SHALL BE INSPECTED DAILY FOR FLUID 4 LEAKS AND REPAIRED, PRIOR TO USE WITHIN 150-FEET, IF A LEAK IS DETECTED. THE CONTRACTOR MUST KEEP DAILY INSPECTION REPORTS IN A DIARY.
- 5. PUMPS USED FOR DEWATERING SHALL HAVE INTAKE SCREENS THAT MEET THE MOST CURRENT VERSION OF NMFS' AND OFDW' FISH SCREEN CRITERIA OR BE OPERATED IN AN AREA WHERE FISH ARE NOT ABLE TO ENTER.
- AT COMPLETION OF PROJECT RE-WATER THE CONSTRUCTION SITE SLOWLY TO PREVENT LOSS OF SURFACE FLOW DOWNSTREAM, AND TO PREVENT RELEASE OF SUSPENDED SEDIMENT.

FLOW CONDITIONS DURING IN-WATER WORK

THE PROJECT WILL BE IMPLEMENTED DURING THE IN-STREAM WORK WINDOW JULY 1 - SEPTEMBER 15. ANTICIPATED FLOWS ARE SUMMARIZED IN TABLE 1 (THIS DRAWING).

FISH PASSAGE

THERE IS CURRENTLY NO FISH PASSAGE DURING THE IN-WATER WORK WINDOW (JULY 1 -SEPTEMBER 15) DUE TO SIGNIFICANT JUMP HEIGHTS AND LACK OF FLOW. THEREFORE, NO FISH PASSAGE WILL BE PROVIDED DURING CONSTRUCTION

()	1) BEST MANAGEMENT PRACTICES PLAN		
	1" =30'	$\overline{(1)}$	PRESER
	FISH SALVAGE NOTES	ଁ	INSTALL
. (CONTRACTOR SHALL COORDINATE WITH OREGON DEPARTMENT OF FISH AND WILDLIFE	${}$	CHANNE
([ODFW) TO REMOVE EXISTING FISH AT THE PROJECT SITE PRIOR TO ISOLATION AND DEWATERING THE AREA. CONTRACTOR SHALL NOTIFY ODFW A MINIMUM OF 10 BUSINESS DAYS PRIOR TO BEGINNING WORK AREA ISOLATION. FISH SALVAGE TO BE CONDUCTED BY	3	INSTALL WORK A

- TRAINED FISHERIES BIOLOGISTS AND PER ODFW AND NOAA RULES. IF POSSIBLE ALLOW FISH SPECIES TO MIGRATE OUT OF WORK AREA. IF NECESSARY, A BACKPACK ELECTROSHOCKER OR SEINE NET (MADE FROM 9.5 MM STRETCHED NYLON MESH) MAY BE USED TO REMOVE FISH FROM THE ISOLATED WORK AREA.
- IN COFFERDAM WORK AREAS AND OTHER ISOLATED AREAS, WATER WILL BE DRAWN DOWN 2. TO HELP CONSOLIDATE FISH AND IMPROVE SALVAGE EFFORTS. REDUCING WATER VOLUME WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE DONE USING PUMPS FITTED WITH APPROVED FISH SCREENS THAT PREVENT IMPINGEMENT OR ENTRAINMENT OF FISH.
- WATER WILL BE DRAWN DOWN IN A CONTROLLED MANNER WITH FISH SALVAGE CREWS CONTINUOUSLY MONITORING THE PUMPS, NEWLY EXPOSED AREAS, AND FISH NUMBERS FOR CROWDING. IF ISOLATED POCKETS OR POOLS OCCUR, THEY WILL BE DEFISHED AND PUMPING WILL BE REDUCED ONCE MANAGEABLE WATER LEVELS ARE OBTAINED.
- 4. ALL CAPTURED AQUATIC LIFE WILL BE IMMEDIATELY PUT INTO DARK COLORED FIVE GALLON BUCKETS FILLED WITH CLEAN RIVER WATER FOR THE PERIOD BETWEEN CAPTURE AND RELEASE. FISH SPECIES AND LIFE STAGE WILL BE DOCUMENTED AND FISH WILL BE RELEASED IN A SAFE ENVIRONMENT IN THE STREAM.

TABLE 1. ANTICIPATED FLOWS DURING IN-WATER WORK WIN

FLOW DURATION	JULY	AUGUST	SEPTEMBER	WEIGHTED AVERAGE FLOW DURING IWW	
	(cfs) / (GPM)	(cfs) / (GPM)	(cfs) / (GPM)	(cfs) / (GPM)	
95%	± 4 / 1690	± 2 / 1060	± 2 / 1020	± 3 / 1260	30
50%	± 9 / 4010	± 5 / 2130	± 4 / 1920	± 6 / 2690	16
25%	± 12 / 5590	± 6 / 2710	± 6 / 2510	± 8 / 3600	8
10%	± 17 / 7410	± 8 / 3390	± 9 / 3940	± 11 / 4910	4
5%	± 19 / 8710	± 9 / 3970	± 13 / 5800	± 14 / 6160	2

- (4)
- (5) NOTES THIS DRAWING).
- (6)

CONSTRUCTION NOTES

VE AND PROTECT EXISTING VEGETATION.

SEDIMENT FENCE, OR APPROVED EQUIVALENT, AT TOE OF TEMPORARY EL ACCESS (SEE DRAWING 2.7).

FISH BLOCK NET AND EXCLUSION BERM UPSTREAM AND DOWNSTREAM OF REA (SEE DRAWING 2.8). BLOCK NETS OR EXCLUSION BERMS TO REMAIN IN FOR THE DURATION OF THE IN-WATER WORK

INSTALL FLOATING SILT CURTAIN (SEE DETAIL DRAWING 2.8).

USE SUMPED PUMPS WITH SCREENS TO DEWATER ISOLATED WORK AREA (SEE DRAWING 2.8). DISCHARGE PUMPED WATER TO DEWATERING BAG (SEE DRAWING 2.8). REMOVE AQUATIC LIFE FROM ISOLATED WORK AREA (SEE FISH SALVAGE

CONSTRUCT TEMPORARY CHANNEL ACCESS (SEE DRAWING 2.5). SALVAGE AND STOCKPILE ALL TREES REMOVED DURING TEMPORARY CHANNEL ACCESS DEVELOPMENT FOR REUSE IN SITE RESTORATION (SEE DRAWING 4.0).

RESTORE TEMPORARY ACCESS ROUTES AND DISTURBED AREAS TO SIMILAR OR BETTER THAN PRE-WORK CONDITIONS.

RESTORE ALL DAMAGED OR DISTURBED STREAMBANKS TO A NATURAL SLOPE PATTERN AND PROFILE SUITABLE FOR ESTABLISHMENT OF PERMANENT WOODY VEGETATION. RESTORE DISTURBED AREAS OUTSIDE LIMITS OF ROADWAYS WITH NATIVE VEGETATION AT A DISTRIBUTION AND DENSITY THAT MATCHES PRE-PROJECT CONDITIONS. SEE REVEGETATION PLAN ON DRAWING 4.0. IMPLEMENT SHORT-TERM STABILIZATION MEASURES UNTIL PERMANENT EROSION CONTROL MEASURES (PLANT RESTORATION) ARE EFFECTIVE.

AYS OF FLOW 31-DAY MONTH

ഗ Ш

CTIC

RA

GEMENT

MANA

ົດ

ш

 \mathbf{m}

FISH PASSAGE ОР RIVER COUNTY COQUILLE DOUGLAS FORK MIDDLE





6" MIN.









Drawing 15 of 21







- 2. MODIFIED CHANNEL SHALL UTILIZE EXISTING BOULDERS FOR CHANNEL ROUGHNESS AND FILL IN SCOUR HOLE DOWNSTREAM OF FALLS.
- CHANNEL BREAKLINES AND BOULDERS FOR MODIFICATION WILL BE MARKED IN THE 3. FIELD BY THE ENGINEER.

- (DRAWINGS 1.1 TO 1.4). (3)DOWNSTREAM OF FALLS CREST (APPROX. STA. 11+70 TO STA. 12+10). DRAWING 3.1). 5 DIRECTED BY THE ENGINEER. 6 SURFACE FLOW IN LOW-FLOW CHANNEL. \bigcirc BLOCK BERM (SEE DRAWING 2.8).
- (8) REMOVE TEMPORARY CHANNEL ACCESS AND REVEGETATE (SEE DRAWING 4.0).

MODIFY EXISTING BOULDERS IN CHANNEL TO MEET DESIGN PROFILE (SEE DRAWING 3.1), SECTIONS (SEE DRAWING 3.2) AND GRADATION (SEE DRAWING 3.3). EXISTING BOULDERS MAY BE PLACED IN SCOUR HOLE

DESCR

BY MCK

ġ ∘

PROJECT NUMBER RDG-22-274 DRAWING NUMBER 3.L Drawing 16 of 21

벁

A 6/1

MODIFY EXISTING BOULDERS IN SOUTH BANK PASSAGE CHANNEL TO MEET DESIGN PROFILE (SEE

GRADE LOW-FLOW CHANNEL TRANSITIONS FROM MODIFIED CHANNEL TO EXISTING CHANNEL AS

PLACE STREAMBED MATRIX (SEE DRAWING 3.3) IN AND AROUND MODIFIED BOULDERS TO SUPPORT

REMOVE FISH BLOCK NETS AFTER IN-WATER WORK IS COMPLETE. NOTCH LOW-FLOW CHANNEL IN FISH











ESTIMATED QUANTITIES

MATERIAL	EST. VOLUME
SELECT GENERAL BACKFILL	± 30 CY
4-INCH TEMPORARY BERM ROCK	± 50 CY
TEMPORARY ACCESS ROCK	± 80 CY
ODOT RIPRAP, CLASS 100	± 30 CY
STREAMBED MATRIX ROCK	± 120 CY

*NOTE: ESTIMATED VOLUMES ARE "NEAT LINE" ESTIMATES

MATERIAL NOTES

- 1. ALL IMPORTED ROCK MATERIAL SHALL BE FREE OF INVASIVE SPECIES AND CERTIFIED WEED-FREE.
- 2. STREAMBED MATERIALS MAY NOT BE SOURCED FROM AREAS WITHIN ACTIVE CHANNELS AND MAY NOT BE CRUSHED ROCK.
- 3. ALL MATERIALS SHALL BE UNIFORMLY GRADED FROM THE SMALLEST TO LARGEST PARTICLE SIZE SPECIFIED.

SELECT GENERAL **BACKFILL GRADATION**

PERCENT PASSING	AVERAGE PARTICLE	
BY WEIGHT	SIZE (INCHES)	
100	3	
50 - 90	1	
35 MAX.	0.003 (NO. 200)	
SELECT GENERAL BACKFILL SHALL BE WELL-GRADED COMPACTABLE MATERIAL CONTAINING NO PARTICLE WITH ANY DIMENSION GREATER THAN 3 INCHES.		

STREAMBED MATRIX **ROCK GRADATION**

PERCENT PASSING BY WEIGHT	AVERAGE PARTICLE SIZE (INCHES)	
100	2.5	
50 - 90	2	
20 - 50	1.5	
0 - 20	1	
STREAMBED MATRIX ROCK SHALL CLEAN, DURABLE, OPEN-GRADEL ROUNDED AGGREGATE.		

4-INCH TEMPORARY BERM **ROCK GRADATION**

PERCENT PASSING BY WEIGHT	AVERAGE PARTICLE SIZE (INCHES)		
100	4		
50 - 90	3.75		
0 - 50	3.5		
4-INCH TEMPORARY BERM ROCK SHALL BE CLEAN, DURABLE, OPEN-GRADED SUBANGULAR			
AGGREGATE.			

RIPRAP, CLASS 100 GRADATION

PERCENT (BY WEIGHT)	WEIGHT OF ROCK (LB)
20	100 - 60
30	60 - 25
40	25 - 2
10 - 0	2 - 0
RIPRAP SHALL BE HARD, ANGULAR, AND DURABLE ROCK WITHOUT ORGANIC MATTER, SHALE, OR SEAMS.	

TEMPORARY ACCESS ROCK GRADATION

PERCENT PASSING BY WEIGHT	AVERAGE PARTICLE SIZE (INCHES)
100	6
60 - 90	4
40 - 70	3
20 - 50	2
0 - 20	1
2 MAX.	0.2
TEMPORARY ACC	ESS ROCK SHALL BE

CLEAN, DURABLE, OPEN-GRADED SUBANGULAR TO SUBROUNDED AGGREGATE.

BOULDER GRADATION

	DIAMETER BANGE (ET)	
BED	1.5 TO 2.5	
BANKS	2 TO 3	
BENCH	3 TO 5	
CUT SLOPE	4 TO > 6	
BOULDERS SHALL BE MODIFIED FROM EXISTING BOULDERS TO BE SUBANGULAR TO SUBROUNDED.		





FALLS PLANTING SCHEDULE

SPECIES	MIN. ON-CENTER SPACING (FT)	SIZE	QUANTITY
ł	40	5 GALLON	2
PHYLUM	40	5 GALLON	2
A	10	1 GALLON	8
OSUM	5	1 GALLON	15
	15	TALL 1 GALLON	4
ISIS	10	LIVE STAKE	12
тим	10	1 GALLON	2
ERULEA	5	1 GALLON	5
EED-FREE STRAW		TOTAL	50
4.1).		SUBTOTAL TREES	20
		SUBTOTAL SHRUBS	30



COQUILLE RIVER FISH PASSAG 0R DOUGLAS COUNTY,

ш

AN

REVEGETATION MIDDLE FORK



TRIBUTARY PLANTING SCHEDULE

SPECIES	MIN. ON-CENTER SPACING (FT)	SIZE	QUANTITY
	20	TALL 1 GALLON	2
HYLUM	30	5 GALLON	2
4	10	1 GALLON	2
ULARIS	5	1 GALLON	5
OSUM	5	1 GALLON	5
ED-FREE STRAW 4.1).		TOTAL	16
		SUBTOTAL TREES	4
		SUBTOTAL SHRUBS	12

REVEGETATION NOTES

- 1. STOCKPILE ALL WOODY MATERIAL, NATIVE VEGETATION, TOPSOIL, AND NATURAL RIVER MATERIAL DISPLACED DURING CONSTRUCTION AND USE FOR SITE RESTORATION. THE STOCKPILED MATERIALS SHALL BE INCORPORATED INTO COVER OF DISTURBED AREAS TO RESTORE THE SITE TO NATURAL CONDITIONS WHILE MINIMIZING THE POTENTIAL FOR EROSION
- 2. ALL DISTURBED AREAS OUTSIDE OF THE EXISTING PAVEMENT LIMITS SHALL BE BROADCAST SEEDED WITH A TEMPORARY "EROSION CONTROL" SEED MIX AND COVERED WITH STERILE STRAW.
- THE EROSION CONTROL SEED MIX SHALL BE A NATIVE SEED MIX CONSISTING OF RED 2.1. FESCUE, BLUE WILDRYE AND STERILE CEREAL RYES. BLM MAY BE ABLE TO PROVIDE THE EROSION CONTROL SEED MIX.
- THE SEED MIX SHALL BE APPLIED AT A RATE OF 30 POUNDS PER ACRE AND RAKED 2.2. ONE-QUARTER INCH INTO THE SOIL AND COMPACTED WITH A 5,000 POUND OR LESS TRACKED VEHICLE AND
- 2.3. STERILE STRAW MULCH SHALL BE APPLIED OVER SEEDED AREAS AT A RATE OF 2 TONS PER ACRE OR APPROXIMATELY 1-2 INCHES THICK.
- 3. ALL PLANT MATERIAL MUST BE CLASSIFIED AS NATIVE FROM THIS REGION AND NON-CLONAL IN ORIGIN. ALL NATIVE PLANT MATERIAL TO BE USED IN PLANTING AREAS SHALL ORIGINATE FROM PARENT SOURCES WITHIN 50 MILES OF SITE. SEED SOURCE MUST BE AS LOCAL AS POSSIBLE.
- 4. INSTALL TREE AND SHRUB SPECIES IN RANDOM GROUPINGS, AVOIDING LINEAR ROWS OR AS DIRECTED IN FIELD, WITHIN CLOSE PROXIMITY OF EXISTING PLANTINGS OR NEWLY PLANTED MATERIAL. THE INTENT IS TO REPLICATE NATURAL PLANT COMMUNITIES BY PROVIDING A LAYERED UNDERSTORY CANOPY WITH A MIXTURE OF TREES.
- 5. THE PLANTING AND SEEDING AREA IS TO COVERED WITH TOPSOIL. IF THIS TOPSOIL IS DEEMED BY PROJECT ENGINEER TO BE INADEQUATE, IMPORTED MATERIAL SHALL BE USED TO POCKET PLANT THE PLANTS.
- 6. THOROUGHLY WATER ALL PLANTS IMMEDIATELY FOLLOWING INSTALLATION TO PROVIDE MAXIMUM SOIL CONTACT AND TO ELIMINATE AIR POCKETS. AFTER PLANTING EACH PLANT, PROVIDE A TWO (2) INCH LAYER OF MULCH AROUND DISTURBED AREA.
- 7. NO PESTICIDES, INCLUDING HERBICIDE, WILL BE ALLOWED WITHIN 150 FT OF THE WATER. MECHANICAL, HAND, OR OTHER METHODS MAY BE USED TO CONTROL WEEDS AND UNWANTED VEGETATION. FERTILIZER APPLICATION WITHIN 50 FT OF THE WATER IS NOT ALLOWED.



GROUND (1)(2)LEVEL 111 (XYY) بلالاللال IN NILN 1 KTT RITE KL LLKK (AN) PER BALI TO 6" SOIL MIN 1.1 4 SLOPES 34 0F 3. MIN. 2' WIDER THAN BALL ADD ENOUGH TAMPED SOIL IN THE REMOVE PLANT FROM CONTAINER AND BOTTOM OF THE HOLE TO SET THE BALL FILL HOLE 3/4 FULL OF TAMPED SOIL. AT OR SLIGHTLY HIGHER THAN THE ORIGINAL PLANTING DEPTH (4)(3) - MINIMUM OF 2" FROM TRUNK VIVIVIVIVIV 1888 LILLY V KI V / VILL WATER FILL THE REMAINING 1/4 OF THE HOLE UNLESS SOIL IS POORLY DRAINED, WITH WATER TO REMOVE AIR POCKETS MOUND SOIL AROUND EDGES OF HOLE AND SETTLE THE SOIL. FINISH FILLING 4" TO 6" HIGH. ADD A MINIMUM OF 4" OF THE HOLE WITH SOIL AFTER ALL THE APPROVED MULCHING MATERIAL. KEEP WATER HAS DRAINED. MULCH 2" MIN. FROM TRUNK. **CONTAINER PLANTING DETAIL**

- INSTALLATION

NOT TO SCALE

LIVE STAKE PLANTING NOTES:

2. LIVE STAKES SHALL HAVE MINIMUM DIAMETER OF 1.5" AND MINIMUM LENGTH 4'. THE STAKES SHALL BE CUT FROM NEARBY PLANTS IF POSSIBLE, OR LOCAL 'ECOTYPES'. STAKES SHALL HAVE SIDE BRANCHES CLEANLY REMOVED WITH BARK INTACT, BASAL ENDS CUT AT AN

4. STAKES SHALL BE INSTALLED WHILE IN THE DORMANT STAGE, NOVEMBER 1 TO FEBRUARY

STAKES SHALL BE INSTALLED WITH 80% OF THE STAKE LENGTH INSTALLED INTO THE GROUND WITH FIRM SOIL IN CONTACT WITH THE WILLOW STAKE. A PIECE OF REBAR SHALL

7. ALTERNATE INSTALLATION PROCEDURES MAY BE USED UPON CONSULTATION WITH

REFER TO NATURAL RESOURCES CONSERVATION SERVICE TECHNICAL NOTE 38, "SUGGESTIONS FOR I INSTALLING HARDWOOD CUTTINGS (SLIPS, WHIPS, LIVE STAKES, POLES, POSTS) AND LIVE FASCINES (PACIFIC NORTHWEST REGION, WEST OF CASCADES)"

CONTAINER PLANTING NOTES:

CONTAINER PLANTS SHALL BE OF THE SIZE SPECIFIED IN THE PLANTING SCHEDULE (SEE DRAWING 4.0).

2. MINIMIZE THE TIME BETWEEN DELIVERY OF PLANTS AND

INSTALL CONTAINER PLANTS PER DETAIL 2 AND ON-CENTER SPACING PER PLANTING SCHEDULE.

4. ALTERNATE INSTALLATION PROCEDURES MAY BE USED UPON CONSULTATION WITH PROJECT ENGINEER.



Drawing 21 of 21